

Schedule of Work

Name of Work: Electrical Renovation Work for Room No. 57 (Deans Office) situated in the Main of IACS

Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)
1	Wiring for light point / fan point / exhaust fan point / call bell point with 1.5sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate , suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.				
	Group C	4	Point		
2	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.				
a)	2X1.5sq.mm+ 1X1.5sq.mm earth wire	80	Metre		
b)	2X4sq.mm +1X4sq.mm earth wire	100	Metre		
3	Supplying and drawing following pair 0.5mm dia FRLS PVC insulated anealed copper conductor, unarmored telephone cable in the existing surface/recessed steel/PVC conduit as required.				
	2 Pair	120	Metre		
4	Suplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recessed conduit as required.				
	20mm	80	Metre		
5	Supplying and fixing of following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc. as required.				
	a) 8 Module	3	Nos		
	b) 3 Module	2	Nos		
6	Supplying and fixing of following modular switch/socket on the existing modular plate & switch box including connections but excluding plate etc. as required.				
	a) 5/6 amp switch	3	Nos.		
	b) 3 pin 5/6 amp socket	9	Nos.		
	c) 6 pin 15/16A socket outlet	2	Nos.		

Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)
7	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in reces, including providing and fixing 6 pin 5/6 & 15/16 amps modular socket outlet and 15/16 amps modular switch, conection etc. as required.	4	Nos.		
8	Supplying & Fixing of 18W Decorative fitting (Cat. No.Down Lighter FBS 100, 1xPL-C/2P 18W of M/s Philips or equivalent model) with lamps on wall/false ceiling including connection with 1.5 sq. mm FRLS PVC insulated copper conductor, single core cable and earthing etc. as required.	1	No		
9	Supplying & Fixing of 2x36 W Decorative Fluorescent tube light fitting (Cat. No. TBS 518, 2xTL-D36W EBT of M/s Philips or equivalent model) with lamps on wall/false ceiling including connection with 1.5 sq. mm FRLS PVC insulated copper conductor, single core cable and earthing etc. as required.	3	Nos.		
10	Supply & Fixing RJ11 Modular Type of Telephone Outlet in G.I. Box with cover, recessed in wall / Furniture.	3	Nos.		
11	Supplying & Fixing of modular type 20Amp A.C. starter switch with GI Box complete recessed in wall.	2	Nos.		
				Total	
				Add Contingencies @ 5%	
				Grand Total (Rs.)	
				Say (Rs.)	

