

<b>ESTIMATE CUM SCHEDULE OF WORKS.</b>					
<b>NIT NO.- IACS/WS/SB/14/02</b>			<b>DATE.- 07.01.2014</b>		
<b>Name of Work: Electrical Work at Main Building at room no 8 in SSP.Dept</b>					
<b>Sl No.</b>	<b>Name of work</b>	<b>Qunt</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>
1	Ear thing with copper earth plate 600 mm x 600 mm x 3mm thick by copper rivet & nut-bolts M10 with copper strip 25 x 5 mm including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. with charcoal /coke and salt as required.	1	No		
2	Providing and fixing 25 mm x 5 mm copper strip on surface along with heavy duties porcelain base with nut bolt or in recess for connections etc. as required.	40	Rm		
				Total	
3	Miscellaneous works including new work, procurement of new item as per the requirement of the Engineer-in-charge to expedite the work @ 10% of the total amount up to previous item		LS		
		<b>Grand Total</b>			

**Signature of the Contractor with date & seal**